



**Procurement Office  
Kaye B. Syfrett  
Purchasing Manager  
31 Klein Street, Room 208  
Walterboro, SC 29488  
Phone: (843) 782-0504**

**CC-11 New Road Construction  
Bids will be accepted until  
11:00am, Tuesday, December 31, 2013**

**Addendum #2**

This addendum is dated December 20, 2013  
Answers to questions

1. The Unclassified Excavation quantities seem low. Can the engineer double-check the quantity and confirm? **Answer:** There was an error in the unclassified quantities shown on the bid sheet. The quantities were recalculated and the quantity for "Unclassified Excavation" has increased from 3,450 cy to 5,242 cy. See attached revised Bid Form.
2. Can the excess material be left on-site and if so, where? **Answer:** Per the approved SCDHEC permit, there is no space within the Limits of Disturbance to waste the excess material. The engineer is going to submit a modification to SDHEC on our Land Disturbance Permit to provide a place to dispose of excess material somewhere on-site. However, at this time the contractor needs to plan disposing any excess material off-site.

BID FORM VENTURE PARK ROADWAY FOR COLLETON COUNTY, SOUTH CAROLINA <b>CC-11 NEW ROAD CONSTRUCTION</b>						
ITEM NO.	SCDOT BID ITEM NO.	DESCRIPTION	EST. QTY	UNIT	UNIT COST	TOTAL AMOUNT
1	1031000	Mobilization	1.00	LS		\$ -
2	1050800	Construction Stakes, Lines, & Grades	1.00	LS		\$ -
3	1071000	Traffic Control	1.00	LS		\$ -
4	2011001	Clearing & Grubbing	3.32	AC		\$ -
5	2025000	REM.&DISP.OF EXIST ASPH. PVMT.	285.00	SY		\$ -
6	2031000	Unclassified Excavation	5,242.00	CY		\$ -
7	3050108	Graded Agg. Base Course (8" Unif.)	5,892.00	SY		\$ -
8	4010005	Prime Coat	1,768.00	GAL		\$ -
9	4011004	Liquid Asphalt Binder PG64-22	68.00	TON		\$ -
10	4011004	Liquid Asphalt Binder PG64-22 - Existing Venture Roadway Surface	33.00	TON		\$ -
11	4020320	Hot Mix Asphalt Intermediate Course Type B (2" Uniform)	650.00	TON		\$ -
12	4030320	Hot Mix Asphalt Surface Course - Type B (2" Uniform)	650.00	TON		\$ -
13	4030320	Hot Mix Asphalt Surface Course - Type B (2" Uniform) - Existing Venture Roadway Surface	620.00	TON		\$ -
14	609115B	Pavement Markings (Temporary Paint) - 4" Yellow Solid Lines	2,400.00	LF		\$ -
15	6241074	4" Yellow Solid Lines (Pvt. Edge Lines) - Perm. Pvm. Markings	2,400.00	LF		\$ -
16	609115B	Pavement Markings (Temporary Paint) - 4" Yellow Solid Lines - Existing Venture Roadway Surface	1,640.00	LF		\$ -
17	6241074	4" Yellow Solid Lines (Pvt. Edge Lines) - Perm. Pvm. Markings - Existing Venture Roadway Surface	1,640.00	LF		\$ -
18	6271025	24" White Solid Lines (Stop/Diagonal Lines) - Thermoplastic - 125 mil. - Existing Venture Roadway Surface	75.00	LF		\$ -
19	7141112	15" RC Pipe Cul. - Class III	52.00	LF		\$ -
20	7141113	18" RC Pipe Cul. - Class III	46.00	LF		\$ -
21	7141114	24" RC Pipe Cul. - Class III	78.00	LF		\$ -
22	7142512	15" R.C. BEV. END SECTN-CL3	1.00	EA		\$ -
23	7142513	18" R.C. BEV. END SECTN-CL3	2.00	EA		\$ -
24	7142514	24" R.C. BEV. END SECTN-CL3	2.00	EA		\$ -
25	7197120	Adjust Manhole	1.00	EA		\$ -
26	N/A	Rip Rap (Class B)	76.00	SY		\$ -
27	8048205	Geotextile for Erosion Control Under Rip Rap (Class 2) Type B	76.00	SY		\$ -
28	8100101	Permanent Cover	2.10	AC		\$ -
29	8100200	Temporary Cover	2.10	AC		\$ -
30	8152007	Sediment Tubes	26.00	LF		\$ -
31	8153000	Silt Fence	3,850.00	LF		\$ -
32	8153090	Repair/Replace Silt Fence	3,850.00	LF		\$ -
33	8154011	Temporary Porous Baffle	150.00	LF		\$ -
34	8154012	Temporary Floating Skimmer	1.00	EA		\$ -
35	8154050	Removal of Silt Retained By Silt Fence	3,850.00	LF		\$ -
36	8156490	Stabilized Construction Entrance	267.00	SY		\$ -
37	N/A	Riprap Filter Berm	1.00	EA		\$ -
38	N/A	Temporary Riser W/ Trash Rack	1.00	EA		\$ -
<b>TOTAL OF BID</b>					<b>\$</b>	<b>-</b>

Project Approach - Please attach an outline and schedule for completing this project.

\_\_\_\_\_  
Company Name

\_\_\_\_\_  
Address City, State, Zip Telephone number

\_\_\_\_\_  
Authorized Signature Print Email Address

**THIS PAGE MUST BE COMPLETED AND SUBMITTED AS PART OF YOUR BID**