



**Capital Projects & Purchasing Department  
113 Mable T. Willis Blvd.  
Walterboro, SC 29488  
843.539.1968**

---

**BID: CTC-10**

**GREENWAY TRAIL PROJECT**

**BIDS DUE: Wednesday, March 15, 2017 @ 11:00am**

**ADDENDUM 1**

**DATED: MARCH 2, 2017**

A) The requirement for the successful bidder to hold a General Contractor's license is hereby removed from the requirements of the bidder.

B) The following questions have been submitted for clarification:

- 1) Is silt fence to be placed on both sides of the entire length of the project? No, only in critical areas as per the permit requirements.
- 2) We think the embankment stone will be really contaminated with dirt, grass, leaves, pine straw and etc. Instead of hauling this material to stockpile can we roll this material to each side to box our new stone base in with? Yes, it has been brought to our attention the embankment does not have the typical railroad stone base on the majority of the area in which we are working; therefore, the excavated material will be placed on the shoulders and not carried to the trailhead. Placement of material on the shoulders will now be included in the "FINE GRADING" line item. The "FINE GRADING\*\*" line item description is hereby changed to the following:

FINE GRADING\*\* - Grade trail to drain with proper cross slope and remove 4" of existing material prior to placement of the 6" GABC. The removed material shall be used on the shoulder of the trail. Placement and grading cost of this excavated material to be included in this line item.